

## **Helix Reinforced concrete provided**

- Labor Savings: 72% 65 hrs per vault
- Decrease In Steel: 71% 3,200 fewer lbs
- More Cost Effective Production
- **More Efficient Operation**
- Safer Manufacturing Environment

## **Project Details**

Category: Precast

Contractor: Colorado Precast Location: Loveland, CO USA Application: 15,500 Gallon Vault Original Design: Rebar & Mesh

Helix Design: Hybrid with 45 lbs/yd3

ICC -ES 3949 | UES ER 279








# Precast Vault 15,500 Gallon Vault


Produced by Colorado Precast, Loveland, CO, these 15,500 gallon vaults were originally designed with conventional rebar and mesh. Each tank required about 4,500 pounds of rebar and mesh and 90 hours of labor to prepare, tie and install the steel reinforcement. The Helix design was able to reduce this to only 810 lbs of steel. It reduced labor as well. "The best part is the removal of the bent u-bars of rebar. Those are so labor intensive and typically don't fit very well since the form is tapered. It's constant fight to make those fit and they don't end up where I want them. I'm pretty thrilled with how the Helix is working with our designs. It is saving a lot of labor." - Colorado Precast Engineer Kim Fenstress

The combined material and labor savings allowed Colorade Precast to produce a higher performing and higher quality product for their customer while being more cost effective and providing more efficient and safer manufacturing operations



The original design included 4,500 lbs of rebar and mesh and took 90 hours of labor to install the reinforcement.






#### SIDE VIEW OF VAULT

### **Helix Hybrid Design**

The Helix Hybrid design reduced the conventional steel by 71% and only requires 810 lbs of Helix. Using Helix also saved 65 hours of labor.



SIDE VIEW OF VAULT

